

GOVERNMENT OF MAHARASHTRA - PUBLIC WORKS DEPARTMENT (ELECTRICAL WING)

Abstract of Technical Sanction Estimate - Electrical Installation to New Academic Building, Zilla Parishad High School, Sinnar, Dist. Nashik

Estimate No: EST/ELE/NSK/2024-25/017 TS No: TS/ELE/NSK/2024-25/041 dt. 19/08/2024 CSR 2024-25 (Nashik region)

Item No	Short Description	Unit	Material Rate	Labour Rate	Rate	Quantity	Amount
3-1-1	Supplying and erecting ceiling fan 1200 mm sweep 5 star with down rod accessories	No				16	
1-9-1	Concealed type light point wiring with 1.5 sq.mm (1.5+1E) FR copper wire in provided concealed pipes	Point				84	
1-9-2	Concealed type independent plug point wiring 2.5 sq.mm with modular accessories	Point				22	
1-9-6	Concealed ceiling fan point wiring 1.5 sq.mm (2+1E) FR copper with hook box	Point				16	
1-9-10	Modular electronic fan regulator with 2M plate GI box	No				16	
2-1-3	LED batten luminaire 20 W 4 ft 6500 K polycarbonate body with driver	No				96	
2-1-1	LED panel luminaire 18 W 1200x300 mm surface mounted 6500 K	No				42	
1-O-1	Supplying & laying 20 mm dia PVC conduit concealed in wall / ceiling with bends & couplers	m				620	
	<i>(contd.) with necessary bends, couplers, junction boxes, cutting and making good the wall complete as per specification No: WG-CP/PVC.</i>						
1-1-2	Supplying and laying 25 mm dia. PVC conduit concealed in wall / ceiling	m				340	
1-3-3	S&E; mains with 2x4 sq.mm FRLSH copper PVC insulated wire in provided conduit	m				260	
1-3-6	S&E; mains with 3x4 sq.mm FRLSH copper PVC insulated wire in provided conduit	m				190	
6-1-1	S&F; SPN distribution board 8 way single door with copper bus bar	No				4	
6-2-1	S&F; MCB single pole 6A to 32A C curve ISI marked	No				48	
6-2-4	S&F; RCCB double pole 40A 30 mA sensitivity	No				6	
7-2-4	S/E&T; FR XLPE armoured cable 1100 V 3.5 core 16 sq.mm copper with glands and lugs	m				120	
9-1-1	Providing earthing with GI earth plate 60x60x0.6 cm with salt charcoal and chamber	No				3	
9-2-3	S&F; GI strip 25x6 mm as earth continuity conductor with clamps	m				90	
14-3-1	Testing & commissioning of internal installation including megger test per point	Point				320	
11-2-1	Providing and fixing 40 W LED street light luminaire with programmable driver (non-schedule / new item)	No				6	
	TOTAL						
	<i>Note: Item No. 11-2-1 is a new item approved by the competent authority and is not covered in the current Schedule of Rates - rate to be supported by market quotation.</i>						