

ELECTRICAL INSTALLATION TO NEW ACADEMIC BUILDING - ZILLA PARISHAD HIGH SCHOOL, SINNAR

PWDE/ELE/NASHIK/2024-25/017 | Division: PWD Electrical Division, Nashik | Circle: Nashik Circle

Name of Work	Electrical Installation to New Academic Building - Zilla Parishad High School, Sinnar	Project Code	PWDE/ELE/NASHIK/2024-25/017
Scheme / Head	District Annual Plan 2024-25	Name of Agency	M/s Vidarbha Electricals Pvt. Ltd.
Estimate No.	EST/ELE/NSK/2024-25/017	Technical Sanction No. / Date	TS/ELE/NSK/2024-25/041 dt. 19/08/2024
Agreement No.	AG/ELE/NSK/2024-25/009	MB No. / Financial Year	MB-01 / 2024-25
Tendered Amount (Estimate)	Rs. 13,56,630	CSR Applicable	Electrical CSR 2024-25 - Nashik region
Measurement Period	18/01/2025 to 18/01/2025	Engineer in Charge	Er. Sneha Kulkarni (Junior Engineer (Electrical))

Item No.	Description of Item (as per Master CSR) / Location	Unit	No.	Length (m)	Breadth (m)	Height / Depth (m)	Quantity	Rate (Rs.)	Amount (Rs.)
1 CSR 1-9-1	Item 1 CSR Code 1-9-1 Point Concealed type light / fan / bell point wiring with 1.5 sq.mm (1.5 + 1E) FR grade copper wire in provided concealed pipes, terminating on modular accessories in box, including earthing and required accessories as per specification No: WG-PW/CW.	Point							
1.1	Ground Floor - Head Master Cabin Joint measurement recorded in presence of JE & contractor representative.	Point	15	1			15	495	7,425
1.2	Ground Floor - Office Room 1 Joint measurement recorded in presence of JE & contractor representative.	Point	68	1			68	495	33,660
	Total for Item	Point					83	495	41,085
2 CSR 1-9-2	Item 2 CSR Code 1-9-2 Point Concealed type independent plug point wiring with 2.5 sq.mm (2.5 + 1E) FR grade copper wire in provided concealed pipes with modular socket, switch and earthing as per specification No: WG-PW/CW.	Point							
2.1	Ground Floor - Head Master Cabin Joint measurement recorded in presence of JE & contractor representative.	Point	12	1			12	605	7,260
2.2	Ground Floor - Office Room 1 Joint measurement recorded in presence of JE & contractor representative.	Point	6	1			6	605	3,630
2.3	Ground Floor - Office Room 2 Joint measurement recorded in presence of JE & contractor representative.	Point	2	1			2	605	1,210
2.4	Ground Floor - Store Room Joint measurement recorded in presence of JE & contractor representative.	Point	2	1			2	605	1,210
	Total for Item	Point					22	605	13,310
3 CSR 1-9-3	Item 3 CSR Code 1-9-3 Point Concealed type 6 A plug point wiring with 1.5 sq.mm (2 + 1E) FRLSH copper wire, modular accessories, box and earthing as per specification No: WG-PW/CW.	Point							

FORM No. 23 - MEASUREMENT BOOK

MB No. MB-01

GOVERNMENT OF MAHARASHTRA | PUBLIC WORKS DEPARTMENT (ELECTRICAL WING)

CSR 2024-25 / Nashik

Item No.	Description of Item (as per Master CSR) / Location	Unit	No.	Length (m)	Breadth (m)	Height / Depth (m)	Quantity	Rate (Rs.)	Amount (Rs.)
3.1	Ground Floor - Head Master Cabin Joint measurement recorded in presence of JE & contractor representative.	Point	2	1			2	540	1,080
3.2	Ground Floor - Office Room 1 Joint measurement recorded in presence of JE & contractor representative.	Point	6	1			6	540	3,240
3.3	Ground Floor - Office Room 2 Joint measurement recorded in presence of JE & contractor representative.	Point	2	1			2	540	1,080
3.4	Ground Floor - Store Room Joint measurement recorded in presence of JE & contractor representative.	Point	8	1			8	540	4,320
	Total for Item	Point					18	540	9,720
4 CSR 1-9-4	Item 4 CSR Code 1-9-4 Point Concealed type twin light point / two way control point wiring with 1.5 sq.mm (3 + 1E) FR copper wire, two modular switches, box, earthing and accessories as per specification No: WG-PW/CW.	Point							
4.1	Ground Floor - Head Master Cabin Joint measurement recorded in presence of JE & contractor representative.	Point	3	1			3	765	2,295
4.2	Ground Floor - Office Room 1 Joint measurement recorded in presence of JE & contractor representative.	Point	2	1			2	765	1,530
4.3	Ground Floor - Office Room 2 Joint measurement recorded in presence of JE & contractor representative.	Point	2	1			2	765	1,530
4.4	Ground Floor - Store Room Joint measurement recorded in presence of JE & contractor representative.	Point	3	1			3	765	2,295
4.5	First Floor - Class Room 1 Joint measurement recorded in presence of JE & contractor representative.	Point	2	1			2	765	1,530
	Total for Item	Point					12	765	9,180
5 CSR 1-9-5	Item 5 CSR Code 1-9-5 Point Concealed type 16 A power plug point wiring with 4.0 sq.mm (2 + 1E) FRLSH copper wire, modular socket with switch, box and earthing as per specification No: WG-PW/CW.	Point							
5.1	Ground Floor - Head Master Cabin Joint measurement recorded in presence of JE & contractor representative.	Point	2	1			2	830	1,660
5.2	Ground Floor - Office Room 1 Joint measurement recorded in presence of JE & contractor representative.	Point	4	1			4	830	3,320
5.3	Ground Floor - Office Room 2 Joint measurement recorded in presence of JE & contractor representative.	Point	3	1			3	830	2,490
	Total for Item	Point					9	830	7,470
6 CSR 1-9-6	Item 6 CSR Code 1-9-6 Point Concealed type ceiling fan point wiring with 1.5 sq.mm (2 + 1E) FR copper wire, fan hook / clamp box on RCC slab, modular regulator, earthing and accessories as per specification No: WG-PW/CW.	Point							
6.1	Ground Floor - Head Master Cabin Joint measurement recorded in presence of JE & contractor representative.	Point	9	1			9	630	5,670
6.2	Ground Floor - Office Room 1 Joint measurement recorded in presence of JE & contractor representative.	Point	2	1			2	630	1,260

FORM No. 23 - MEASUREMENT BOOK

MB No. MB-01

GOVERNMENT OF MAHARASHTRA | PUBLIC WORKS DEPARTMENT (ELECTRICAL WING)

CSR 2024-25 / Nashik

Item No.	Description of Item (as per Master CSR) / Location	Unit	No.	Length (m)	Breadth (m)	Height / Depth (m)	Quantity	Rate (Rs.)	Amount (Rs.)
6.3	Ground Floor - Office Room 2 Joint measurement recorded in presence of JE & contractor representative.	Point	5	1			5	630	3,150
	Total for Item	Point					16	630	10,080
7 CSR 1-9-8	Item 7 CSR Code 1-9-8 Point Concealed type call bell point wiring with 1.5 sq.mm (2 + 1E) FR copper wire, bell push and earthing in concealed box as per specification No: WG-PW/CW.	Point							
7.1	Ground Floor - Head Master Cabin Joint measurement recorded in presence of JE & contractor representative.	Point	1	1			1	390	390
7.2	Ground Floor - Office Room 1 Joint measurement recorded in presence of JE & contractor representative.	Point	1	1			1	390	390
7.3	Ground Floor - Office Room 2 Joint measurement recorded in presence of JE & contractor representative.	Point	1	1			1	390	390
7.4	Ground Floor - Store Room Joint measurement recorded in presence of JE & contractor representative.	Point	1	1			1	390	390
	Total for Item	Point					4	390	1,560
8 CSR 1-9-10	Item 8 CSR Code 1-9-10 Each Supplying and fixing modular electronic fan regulator with 2 M plate, GI box, connections and earthing complete as per specification No: WG-PS/MOD.	Each							
8.1	Ground Floor - Head Master Cabin Joint measurement recorded in presence of JE & contractor representative.	Each	8	1			8	435	3,480
8.2	Ground Floor - Office Room 1 Joint measurement recorded in presence of JE & contractor representative.	Each	7	1			7	435	3,045
	Total for Item	Each					15	435	6,525
9 CSR 1-1-1	Item 9 CSR Code 1-1-1 m Supplying and laying 20 mm dia. PVC conduit concealed in wall / ceiling / slab with necessary bends, couplers, junction boxes, cutting and making good the wall complete as per specification No: WG-CP/PVC.	m							
9.1	Ground Floor - Head Master Cabin Joint measurement recorded in presence of JE & contractor representative.	m	1	204.47			204.47	100	20,447
9.2	Ground Floor - Office Room 1 Joint measurement recorded in presence of JE & contractor representative.	m	1	215.24			215.24	100	21,524
9.3	Ground Floor - Office Room 2 Joint measurement recorded in presence of JE & contractor representative.	m	1	170.71			170.71	100	17,071
	Total for Item	m					590.42	100	59,042
10 CSR 1-1-2	Item 10 CSR Code 1-1-2 m Supplying and laying 25 mm dia. PVC conduit concealed in wall / ceiling / slab with necessary bends, couplers, junction boxes, cutting and making good the wall complete as per specification No: WG-CP/PVC.	m							
10.1	Ground Floor - Head Master Cabin Joint measurement recorded in presence of JE & contractor representative.	m	1	38.28			38.28	125	4,785

FORM No. 23 - MEASUREMENT BOOK

MB No. MB-01

GOVERNMENT OF MAHARASHTRA | PUBLIC WORKS DEPARTMENT (ELECTRICAL WING)

CSR 2024-25 / Nashik

Item No.	Description of Item (as per Master CSR) / Location	Unit	No.	Length (m)	Breadth (m)	Height / Depth (m)	Quantity	Rate (Rs.)	Amount (Rs.)
10.2	Ground Floor - Office Room 1 Joint measurement recorded in presence of JE & contractor representative.	m	1	101.81			101.81	125	12,726.25
10.3	Ground Floor - Office Room 2 Joint measurement recorded in presence of JE & contractor representative.	m	1	75.39			75.39	125	9,423.75
10.4	Ground Floor - Store Room Joint measurement recorded in presence of JE & contractor representative.	m	1	37.77			37.77	125	4,721.25
10.5	First Floor - Class Room 1 Joint measurement recorded in presence of JE & contractor representative.	m	1	74.26			74.26	125	9,282.50
	Total for Item	m					327.51	125	40,938.75
11 CSR 1-1-4	Item 11 CSR Code 1-1-4 m Supplying and laying 20 mm dia. 16 gauge rigid steel conduit on surface / concealed with couplers, bends, hooks, saddles, painting with two coats of anti-corrosive paint, earthing continuity complete as per specification No: WG-CP/RSC.	m							
11.1	Ground Floor - Head Master Cabin Joint measurement recorded in presence of JE & contractor representative.	m	1	52.18			52.18	275	14,349.50
11.2	Ground Floor - Office Room 1 Joint measurement recorded in presence of JE & contractor representative.	m	1	37.34			37.34	275	10,268.50
11.3	Ground Floor - Office Room 2 Joint measurement recorded in presence of JE & contractor representative.	m	1	84.82			84.82	275	23,325.50
	Total for Item	m					174.34	275	47,943.50
12 CSR 1-1-6	Item 12 CSR Code 1-1-6 Each Supplying and fixing GI concealed box (8 module) with cover plate for modular switches / sockets including cutting and making good complete as per specification No: WG-CP/MOD.	Each							
12.1	Ground Floor - Head Master Cabin Joint measurement recorded in presence of JE & contractor representative.	Each	2	1			2	220	440
12.2	Ground Floor - Office Room 1 Joint measurement recorded in presence of JE & contractor representative.	Each	6	1			6	220	1,320
12.3	Ground Floor - Office Room 2 Joint measurement recorded in presence of JE & contractor representative.	Each	34	1			34	220	7,480
12.4	Ground Floor - Store Room Joint measurement recorded in presence of JE & contractor representative.	Each	12	1			12	220	2,640
12.5	First Floor - Class Room 1 Joint measurement recorded in presence of JE & contractor representative.	Each	61	1			61	220	13,420
	Total for Item	Each					115	220	25,300
13 CSR 1-3-3	Item 13 CSR Code 1-3-3 m Supplying and erecting mains with 2 x 4 sq.mm FRLSH copper PVC insulated wire laid in provided conduit / trunking / inside pole / bus bars or any other places as per specification No: WG-MA/BW.	m							
13.1	Ground Floor - Head Master Cabin Joint measurement recorded in presence of JE & contractor representative.	m	1	32.10			32.10	150	4,815

FORM No. 23 - MEASUREMENT BOOK

MB No. MB-01

GOVERNMENT OF MAHARASHTRA | PUBLIC WORKS DEPARTMENT (ELECTRICAL WING)

CSR 2024-25 / Nashik

Item No.	Description of Item (as per Master CSR) / Location	Unit	No.	Length (m)	Breadth (m)	Height / Depth (m)	Quantity	Rate (Rs.)	Amount (Rs.)
13.2	Ground Floor - Office Room 1 Joint measurement recorded in presence of JE & contractor representative.	m	1	36.90			36.90	150	5,535
13.3	Ground Floor - Office Room 2 Joint measurement recorded in presence of JE & contractor representative.	m	1	21.64			21.64	150	3,246
13.4	Ground Floor - Store Room Joint measurement recorded in presence of JE & contractor representative.	m	1	29.45			29.45	150	4,417.50
13.5	First Floor - Class Room 1 Joint measurement recorded in presence of JE & contractor representative.	m	1	130.71			130.71	150	19,606.50
	Total for Item	m					250.80	150	37,620
14 CSR 1-3-6	Item 14 CSR Code 1-3-6 m Supplying and erecting mains with 3 x 4 sq.mm FRLSH copper PVC insulated wire laid in provided conduit / trunking / inside pole / bus bars or any other places as per specification No: WG-MA/BW.	m							
14.1	Ground Floor - Head Master Cabin Joint measurement recorded in presence of JE & contractor representative.	m	1	136.91			136.91	220	30,120.20
14.2	Ground Floor - Office Room 1 Joint measurement recorded in presence of JE & contractor representative.	m	1	46.32			46.32	220	10,190.40
	Total for Item	m					183.23	220	40,310.60
15 CSR 1-3-8	Item 15 CSR Code 1-3-8 m Supplying and erecting mains with 3 x 10 sq.mm FRLSH copper PVC insulated wire laid in provided conduit / trunking / inside pole / bus bars or any other places as per specification No: WG-MA/BW.	m							
15.1	Ground Floor - Head Master Cabin Joint measurement recorded in presence of JE & contractor representative.	m	1	16.93			16.93	460	7,787.80
15.2	Ground Floor - Office Room 1 Joint measurement recorded in presence of JE & contractor representative.	m	1	32.57			32.57	460	14,982.20
15.3	Ground Floor - Office Room 2 Joint measurement recorded in presence of JE & contractor representative.	m	1	9.97			9.97	460	4,586.20
15.4	Ground Floor - Store Room Joint measurement recorded in presence of JE & contractor representative.	m	1	18.30			18.30	460	8,418
15.5	First Floor - Class Room 1 Joint measurement recorded in presence of JE & contractor representative.	m	1	38.68			38.68	460	17,792.80
	Total for Item	m					116.45	460	53,567
16 CSR 1-3-11	Item 16 CSR Code 1-3-11 m Supplying and erecting mains with 4 x 10 sq.mm FRLSH copper PVC insulated wire laid in provided conduit / trunking / inside pole / bus bars or any other places as per specification No: WG-MA/BW.	m							
16.1	Ground Floor - Head Master Cabin Joint measurement recorded in presence of JE & contractor representative.	m	1	14.42			14.42	615	8,868.30
16.2	Ground Floor - Office Room 1 Joint measurement recorded in presence of JE & contractor representative.	m	1	21.92			21.92	615	13,480.80
16.3	Ground Floor - Office Room 2 Joint measurement recorded in presence of JE & contractor representative.	m	1	5			5	615	3,075

FORM No. 23 - MEASUREMENT BOOK

MB No. MB-01

GOVERNMENT OF MAHARASHTRA | PUBLIC WORKS DEPARTMENT (ELECTRICAL WING)

CSR 2024-25 / Nashik

Item No.	Description of Item (as per Master CSR) / Location	Unit	No.	Length (m)	Breadth (m)	Height / Depth (m)	Quantity	Rate (Rs.)	Amount (Rs.)
16.4	Ground Floor - Store Room Joint measurement recorded in presence of JE & contractor representative.	m	1	25.08			25.08	615	15,424.20
16.5	First Floor - Class Room 1 Joint measurement recorded in presence of JE & contractor representative.	m	1	21.73			21.73	615	13,363.95
	Total for Item	m					88.15	615	54,212.25
17 CSR 1-5-5	Item 17 CSR Code 1-5-5 Each Supplying and fixing modular switch 6 A / 16 A on 2 M plate with GI box, connections and earthing complete as per specification No: WG-PS/MOD.	Each							
17.1	Ground Floor - Head Master Cabin Joint measurement recorded in presence of JE & contractor representative.	Each	6	1			6	190	1,140
17.2	Ground Floor - Office Room 1 Joint measurement recorded in presence of JE & contractor representative.	Each	26	1			26	190	4,940
17.3	Ground Floor - Office Room 2 Joint measurement recorded in presence of JE & contractor representative.	Each	20	1			20	190	3,800
17.4	Ground Floor - Store Room Joint measurement recorded in presence of JE & contractor representative.	Each	9	1			9	190	1,710
	Total for Item	Each					61	190	11,590
18 CSR 1-5-1	Item 18 CSR Code 1-5-1 Each Supplying and erecting recess type 3 pin plug socket 6 A with piano switch 6 A combined unit erected on polished double wooden block / folded sheet box complete as per specification No: WG-PS/RC.	Each							
18.1	Ground Floor - Head Master Cabin Joint measurement recorded in presence of JE & contractor representative.	Each	6	1			6	170	1,020
18.2	Ground Floor - Office Room 1 Joint measurement recorded in presence of JE & contractor representative.	Each	18	1			18	170	3,060
	Total for Item	Each					24	170	4,080
19 CSR 1-5-2	Item 19 CSR Code 1-5-2 Each Supplying and erecting recess type 6 pin plug socket 16 A with switch 16 A combined unit mounted on sheet steel box with earth terminal complete as per specification No: WG-PS/RC.	Each							
19.1	Ground Floor - Head Master Cabin Joint measurement recorded in presence of JE & contractor representative.	Each	5	1			5	405	2,025
19.2	Ground Floor - Office Room 1 Joint measurement recorded in presence of JE & contractor representative.	Each	4	1			4	405	1,620
	Total for Item	Each					9	405	3,645
20 CSR 2-1-3	Item 20 CSR Code 2-1-3 Each Supplying and erecting LED batten luminaire 20 W, 4 ft, 6500 K, polycarbonate body with driver, complete with connections and earthing as per specification No: LF-LED/BTN.	Each							
20.1	Ground Floor - Head Master Cabin Joint measurement recorded in presence of JE & contractor representative.	Each	87	1			87	1,205	1,04,835

FORM No. 23 - MEASUREMENT BOOK

MB No. MB-01

GOVERNMENT OF MAHARASHTRA | PUBLIC WORKS DEPARTMENT (ELECTRICAL WING)

CSR 2024-25 / Nashik

Item No.	Description of Item (as per Master CSR) / Location	Unit	No.	Length (m)	Breadth (m)	Height / Depth (m)	Quantity	Rate (Rs.)	Amount (Rs.)
20.2	Ground Floor - Office Room 1 Joint measurement recorded in presence of JE & contractor representative.	Each	8	1			8	1,205	9,640
	Total for Item	Each					95	1,205	1,14,475
21 CSR 2-1-1	Item 21 CSR Code 2-1-1 Each Supplying and erecting LED panel luminaire 18 W, 1200 x 300 mm, surface mounted, 6500 K, CRCA sheet housing with diffuser, complete with driver, connections and earthing as per specification No: LF-LED/PNL.	Each							
21.1	Ground Floor - Head Master Cabin Joint measurement recorded in presence of JE & contractor representative.	Each	13	1			13	2,185	28,405
21.2	Ground Floor - Office Room 1 Joint measurement recorded in presence of JE & contractor representative.	Each	29	1			29	2,185	63,365
	Total for Item	Each					42	2,185	91,770
22 CSR 2-1-5	Item 22 CSR Code 2-1-5 Each Supplying and erecting LED bulkhead luminaire 20 W, IP65, die cast aluminium body with toughened glass, complete with driver, connections and earthing as per specification No: LF-LED/BHD.	Each							
22.1	Ground Floor - Head Master Cabin Joint measurement recorded in presence of JE & contractor representative.	Each	11	1			11	1,695	18,645
22.2	Ground Floor - Office Room 1 Joint measurement recorded in presence of JE & contractor representative.	Each	1	1			1	1,695	1,695
	Total for Item	Each					12	1,695	20,340
23 CSR 2-1-9	Item 23 CSR Code 2-1-9 Each Supplying and erecting LED flood light luminaire 100 W, IP66, die cast aluminium housing with toughened glass, surge protection, adjustable bracket, complete with wiring and earthing as per specification No: LF-LED/FL.	Each							
23.1	Ground Floor - Head Master Cabin Joint measurement recorded in presence of JE & contractor representative.	Each	1	1			1	4,365	4,365
23.2	Ground Floor - Office Room 1 Joint measurement recorded in presence of JE & contractor representative.	Each	3	1			3	4,365	13,095
23.3	Ground Floor - Office Room 2 Joint measurement recorded in presence of JE & contractor representative.	Each	3	1			3	4,365	13,095
23.4	Ground Floor - Store Room Joint measurement recorded in presence of JE & contractor representative.	Each	1	1			1	4,365	4,365
23.5	First Floor - Class Room 1 Joint measurement recorded in presence of JE & contractor representative.	Each	2	1			2	4,365	8,730
	Total for Item	Each					10	4,365	43,650
24 CSR 2-1-12	Item 24 CSR Code 2-1-12 Each Supplying and erecting LED street light luminaire 120 W, IP66 with programmable driver, surge protection up to 10 kV, complete with wiring and earthing as per specification No: LF-LED/SL.	Each							
24.1	Ground Floor - Head Master Cabin Joint measurement recorded in presence of JE & contractor representative.	Each	1	1			1	9,365	9,365

FORM No. 23 - MEASUREMENT BOOK

MB No. MB-01

GOVERNMENT OF MAHARASHTRA | PUBLIC WORKS DEPARTMENT (ELECTRICAL WING)

CSR 2024-25 / Nashik

Item No.	Description of Item (as per Master CSR) / Location	Unit	No.	Length (m)	Breadth (m)	Height / Depth (m)	Quantity	Rate (Rs.)	Amount (Rs.)
24.2	Ground Floor - Office Room 1 Joint measurement recorded in presence of JE & contractor representative.	Each	1	1			1	9,365	9,365
24.3	Ground Floor - Office Room 2 Joint measurement recorded in presence of JE & contractor representative.	Each	1	1			1	9,365	9,365
24.4	Ground Floor - Store Room Joint measurement recorded in presence of JE & contractor representative.	Each	1	1			1	9,365	9,365
	Total for Item	Each					4	9,365	37,460
25 CSR 2-1-16	Item 25 CSR Code 2-1-16 Each Supplying and erecting LED emergency light fitting with 2 hours battery backup, 2 x 6 W LED, chargeable type, complete with wiring and earthing as per specification No: LF-EM/LT.	Each							
25.1	Ground Floor - Head Master Cabin Joint measurement recorded in presence of JE & contractor representative.	Each	5	1			5	2,915	14,575
25.2	Ground Floor - Office Room 1 Joint measurement recorded in presence of JE & contractor representative.	Each	1	1			1	2,915	2,915
25.3	Ground Floor - Office Room 2 Joint measurement recorded in presence of JE & contractor representative.	Each	2	1			2	2,915	5,830
	Total for Item	Each					8	2,915	23,320
26 CSR 2-1-17	Item 26 CSR Code 2-1-17 Each Supplying and erecting LED exit sign luminaire with emergency backup 2 hours, ceiling / wall mounted, complete with wiring and earthing as per specification No: LF-EM/EX.	Each							
26.1	Ground Floor - Head Master Cabin Joint measurement recorded in presence of JE & contractor representative.	Each	3	1			3	3,000	9,000
26.2	Ground Floor - Office Room 1 Joint measurement recorded in presence of JE & contractor representative.	Each	1	1			1	3,000	3,000
26.3	Ground Floor - Office Room 2 Joint measurement recorded in presence of JE & contractor representative.	Each	2	1			2	3,000	6,000
	Total for Item	Each					6	3,000	18,000
27 CSR 3-1-1	Item 27 CSR Code 3-1-1 Each Supplying and erecting ceiling fan 1200 mm sweep, 5 star rated, 230 V AC, with down rod, canopy, shackle, blades and 3 core flexible wire, complete with earthing as per specification No: FN/CF.	Each							
27.1	Ground Floor - Head Master Cabin Joint measurement recorded in presence of JE & contractor representative.	Each	2	1			2	3,245	6,490
27.2	Ground Floor - Office Room 1 Joint measurement recorded in presence of JE & contractor representative.	Each	5	1			5	3,245	16,225
27.3	Ground Floor - Office Room 2 Joint measurement recorded in presence of JE & contractor representative.	Each	3	1			3	3,245	9,735
27.4	Ground Floor - Store Room Joint measurement recorded in presence of JE & contractor representative.	Each	6	1			6	3,245	19,470
	Total for Item	Each					16	3,245	51,920

FORM No. 23 - MEASUREMENT BOOK

MB No. MB-01

GOVERNMENT OF MAHARASHTRA | PUBLIC WORKS DEPARTMENT (ELECTRICAL WING)

CSR 2024-25 / Nashik

Item No.	Description of Item (as per Master CSR) / Location	Unit	No.	Length (m)	Breadth (m)	Height / Depth (m)	Quantity	Rate (Rs.)	Amount (Rs.)
28 CSR 3-1-6	Item 28 CSR Code 3-1-6 Each Supplying and erecting exhaust fan 250 mm (10 inch) sweep, metal body with powder coating, shutter type, complete with wiring connections and earthing as per specification No: FN/EX.	Each							
28.1	Ground Floor - Head Master Cabin Joint measurement recorded in presence of JE & contractor representative.	Each	1	1			1	2,470	2,470
28.2	Ground Floor - Office Room 1 Joint measurement recorded in presence of JE & contractor representative.	Each	1	1			1	2,470	2,470
28.3	Ground Floor - Office Room 2 Joint measurement recorded in presence of JE & contractor representative.	Each	5	1			5	2,470	12,350
	Total for Item	Each					7	2,470	17,290
29 CSR 3-1-11	Item 29 CSR Code 3-1-11 Each Supplying and fixing MS fan hook / clamp box concealed in RCC slab for ceiling fan, with hooks, painting and necessary making good complete as per specification No: FN/HK.	Each							
29.1	Ground Floor - Head Master Cabin Joint measurement recorded in presence of JE & contractor representative.	Each	6	1			6	275	1,650
29.2	Ground Floor - Office Room 1 Joint measurement recorded in presence of JE & contractor representative.	Each	5	1			5	275	1,375
29.3	Ground Floor - Office Room 2 Joint measurement recorded in presence of JE & contractor representative.	Each	4	1			4	275	1,100
	Total for Item	Each					15	275	4,125
30 CSR 6-1-1	Item 30 CSR Code 6-1-1 Each Supplying and fixing SPN distribution board, 8 way, single door, powder coated CRCA sheet enclosure, with tinned copper bus bar, neutral link, earth link, din rail and knockouts, complete with earthing as per specification No: DB-SPN.	Each							
30.1	Ground Floor - Head Master Cabin Joint measurement recorded in presence of JE & contractor representative.	Each	3	1			3	3,935	11,805
30.2	Ground Floor - Office Room 1 Joint measurement recorded in presence of JE & contractor representative.	Each	1	1			1	3,935	3,935
	Total for Item	Each					4	3,935	15,740
31 CSR 6-1-3	Item 31 CSR Code 6-1-3 Each Supplying and fixing TPN distribution board, 8 way, double door, powder coated CRCA sheet enclosure with bus bar, neutral and earth links, complete with earthing and connections as per specification No: DB-TPN.	Each							
31.1	Ground Floor - Head Master Cabin Joint measurement recorded in presence of JE & contractor representative.	Each	1	1			1	8,280	8,280
31.2	Ground Floor - Office Room 1 Joint measurement recorded in presence of JE & contractor representative.	Each	1	1			1	8,280	8,280
	Total for Item	Each					2	8,280	16,560

FORM No. 23 - MEASUREMENT BOOK

MB No. MB-01

GOVERNMENT OF MAHARASHTRA | PUBLIC WORKS DEPARTMENT (ELECTRICAL WING)

CSR 2024-25 / Nashik

Item No.	Description of Item (as per Master CSR) / Location	Unit	No.	Length (m)	Breadth (m)	Height / Depth (m)	Quantity	Rate (Rs.)	Amount (Rs.)
32 CSR 6-2-1	Item 32 CSR Code 6-2-1 Each Supplying and fixing MCB single pole 6 A to 32 A, C curve, 10 kA breaking capacity, ISI marked, complete with connections as per specification No: SW/MCB.	Each							
32.1	Ground Floor - Head Master Cabin Joint measurement recorded in presence of JE & contractor representative.	Each	26	1			26	495	12,870
32.2	Ground Floor - Office Room 1 Joint measurement recorded in presence of JE & contractor representative.	Each	21	1			21	495	10,395
	Total for Item	Each					47	495	23,265
33 CSR 6-2-4	Item 33 CSR Code 6-2-4 Each Supplying and fixing RCCB double pole 40 A, 30 mA sensitivity, 10 kA, complete with connections and earthing as per specification No: SW/RCCB.	Each							
33.1	Ground Floor - Head Master Cabin Joint measurement recorded in presence of JE & contractor representative.	Each	2	1			2	3,305	6,610
33.2	Ground Floor - Office Room 1 Joint measurement recorded in presence of JE & contractor representative.	Each	1	1			1	3,305	3,305
33.3	Ground Floor - Office Room 2 Joint measurement recorded in presence of JE & contractor representative.	Each	1	1			1	3,305	3,305
33.4	Ground Floor - Store Room Joint measurement recorded in presence of JE & contractor representative.	Each	1	1			1	3,305	3,305
33.5	First Floor - Class Room 1 Joint measurement recorded in presence of JE & contractor representative.	Each	1	1			1	3,305	3,305
	Total for Item	Each					6	3,305	19,830
34 CSR 7-2-4	Item 34 CSR Code 7-2-4 m Supplying, erecting and terminating FR XLPE insulated, galvanised steel formed wire armoured (strip) cable 1100 V, 3.5 core 16 sq.mm copper conductor with glands and lugs complete as per specification No: CB-LT/CU.	m							
34.1	Ground Floor - Head Master Cabin Joint measurement recorded in presence of JE & contractor representative.	m	1	71.03			71.03	1,045	74,226.35
34.2	Ground Floor - Office Room 1 Joint measurement recorded in presence of JE & contractor representative.	m	1	1			1	1,045	1,045
34.3	Ground Floor - Office Room 2 Joint measurement recorded in presence of JE & contractor representative.	m	1	45.63			45.63	1,045	47,683.35
	Total for Item	m					117.66	1,045	1,22,954.70
35 CSR 7-2-2	Item 35 CSR Code 7-2-2 m Supplying, erecting and terminating FR XLPE insulated, galvanised steel formed wire armoured (strip) cable 1100 V, 3.5 core 6 sq.mm copper conductor with glands and lugs, erected on wall / trusses / pole or laid in trench / pipe as per specification No: CB-LT/CU.	m							
35.1	Ground Floor - Head Master Cabin Joint measurement recorded in presence of JE & contractor representative.	m	1	10.43			10.43	470	4,902.10

FORM No. 23 - MEASUREMENT BOOK

MB No. MB-01

GOVERNMENT OF MAHARASHTRA | PUBLIC WORKS DEPARTMENT (ELECTRICAL WING)

CSR 2024-25 / Nashik

Item No.	Description of Item (as per Master CSR) / Location	Unit	No.	Length (m)	Breadth (m)	Height / Depth (m)	Quantity	Rate (Rs.)	Amount (Rs.)
35.2	Ground Floor - Office Room 1 Joint measurement recorded in presence of JE & contractor representative.	m	1	13.75			13.75	470	6,462.50
35.3	Ground Floor - Office Room 2 Joint measurement recorded in presence of JE & contractor representative.	m	1	12.69			12.69	470	5,964.30
35.4	Ground Floor - Store Room Joint measurement recorded in presence of JE & contractor representative.	m	1	23.81			23.81	470	11,190.70
35.5	First Floor - Class Room 1 Joint measurement recorded in presence of JE & contractor representative.	m	1	20.91			20.91	470	9,827.70
	Total for Item	m					81.59	470	38,347.30
36 CSR 7-4-1	Item 36 CSR Code 7-4-1 Each Supplying and erecting brass double compression type cable gland suitable for 20-25 mm cable with earth tag, lock nut and neoprene ring complete as per specification No: CB/ACC.	Each							
36.1	Ground Floor - Head Master Cabin Joint measurement recorded in presence of JE & contractor representative.	Each	1	1			1	355	355
36.2	Ground Floor - Office Room 1 Joint measurement recorded in presence of JE & contractor representative.	Each	9	1			9	355	3,195
36.3	Ground Floor - Office Room 2 Joint measurement recorded in presence of JE & contractor representative.	Each	2	1			2	355	710
36.4	Ground Floor - Store Room Joint measurement recorded in presence of JE & contractor representative.	Each	4	1			4	355	1,420
36.5	First Floor - Class Room 1 Joint measurement recorded in presence of JE & contractor representative.	Each	7	1			7	355	2,485
	Total for Item	Each					23	355	8,165
37 CSR 7-4-2	Item 37 CSR Code 7-4-2 Each Supplying and crimping heavy duty aluminium / copper cable lug of suitable size with crimping tool and insulation sleeve complete as per specification No: CB/ACC.	Each							
37.1	Ground Floor - Head Master Cabin Joint measurement recorded in presence of JE & contractor representative.	Each	1	1			1	190	190
37.2	Ground Floor - Office Room 1 Joint measurement recorded in presence of JE & contractor representative.	Each	12	1			12	190	2,280
37.3	Ground Floor - Office Room 2 Joint measurement recorded in presence of JE & contractor representative.	Each	6	1			6	190	1,140
37.4	Ground Floor - Store Room Joint measurement recorded in presence of JE & contractor representative.	Each	28	1			28	190	5,320
	Total for Item	Each					47	190	8,930
38 CSR 9-1-1	Item 38 CSR Code 9-1-1 Each Providing earthing with galvanized iron earth plate size 60 x 60 x 0.6 cm, buried in pit with alternate layers of salt and charcoal, connected with watering pipe, funnel, GI strip up to test point and masonry chamber with CI cover, testing and recording the results as per specification No: EA-EP.	Each							

FORM No. 23 - MEASUREMENT BOOK

MB No. MB-01

GOVERNMENT OF MAHARASHTRA | PUBLIC WORKS DEPARTMENT (ELECTRICAL WING)

CSR 2024-25 / Nashik

Item No.	Description of Item (as per Master CSR) / Location	Unit	No.	Length (m)	Breadth (m)	Height / Depth (m)	Quantity	Rate (Rs.)	Amount (Rs.)
38.1	Ground Floor - Head Master Cabin Joint measurement recorded in presence of JE & contractor representative.	Each	1	1			1	13,095	13,095
38.2	Ground Floor - Office Room 1 Joint measurement recorded in presence of JE & contractor representative.	Each	1	1			1	13,095	13,095
38.3	Ground Floor - Office Room 2 Joint measurement recorded in presence of JE & contractor representative.	Each	1	1			1	13,095	13,095
	Total for Item	Each					3	13,095	39,285
39 CSR 9-1-4	Item 39 CSR Code 9-1-4 Each Providing maintenance free chemical earthing with 3 m long electrode, back fill compound, bentonite, test point, chamber with cover, testing and recording of earth resistance as per specification No: EA-CE.	Each							
39.1	Ground Floor - Head Master Cabin Joint measurement recorded in presence of JE & contractor representative.	Each	1	1			1	22,030	22,030
39.2	Ground Floor - Office Room 1 Joint measurement recorded in presence of JE & contractor representative.	Each	1	1			1	22,030	22,030
	Total for Item	Each					2	22,030	44,060
40 CSR 9-2-3	Item 40 CSR Code 9-2-3 m Supplying and fixing GI strip 25 x 6 mm as earth continuity conductor / earth lead with clamps, bolts, painting and connections complete as per specification No: EA-EC.	m							
40.1	Ground Floor - Head Master Cabin Joint measurement recorded in presence of JE & contractor representative.	m	1	20.41			20.41	275	5,612.75
40.2	Ground Floor - Office Room 1 Joint measurement recorded in presence of JE & contractor representative.	m	1	4.51			4.51	275	1,240.25
40.3	Ground Floor - Office Room 2 Joint measurement recorded in presence of JE & contractor representative.	m	1	9.92			9.92	275	2,728
40.4	Ground Floor - Store Room Joint measurement recorded in presence of JE & contractor representative.	m	1	39.54			39.54	275	10,873.50
40.5	First Floor - Class Room 1 Joint measurement recorded in presence of JE & contractor representative.	m	1	11.77			11.77	275	3,236.75
	Total for Item	m					86.15	275	23,691.25
41 CSR 9-3-1	Item 41 CSR Code 9-3-1 Each Supplying and erecting copper lightning protection spike / air termination rod 1 m long with base, fittings and connections to down conductor complete as per specification No: EA-LP.	Each							
41.1	Ground Floor - Head Master Cabin Joint measurement recorded in presence of JE & contractor representative.	Each	1	1			1	8,815	8,815
41.2	Ground Floor - Office Room 1 Joint measurement recorded in presence of JE & contractor representative.	Each	1	1			1	8,815	8,815
	Total for Item	Each					2	8,815	17,630

FORM No. 23 - MEASUREMENT BOOK

Item No.	Description of Item (as per Master CSR) / Location	Unit	No.	Length (m)	Breadth (m)	Height / Depth (m)	Quantity	Rate (Rs.)	Amount (Rs.)
42 CSR 9-4-2	Item 42 CSR Code 9-4-2 Each Earth resistance testing with earth tester, recording of results in prescribed proforma and submission of test report as per specification No: EA/TEST.	Each							
42.1	Ground Floor - Head Master Cabin Joint measurement recorded in presence of JE & contractor representative.	Each	1	1			1	495	495
42.2	Ground Floor - Office Room 1 Joint measurement recorded in presence of JE & contractor representative.	Each	4	1			4	495	1,980
	Total for Item	Each					5	495	2,475
43 CSR 14-3-1	Item 43 CSR Code 14-3-1 Point Testing and commissioning of internal electrical installation including megger test of circuits, polarity test, earth continuity test and submission of test records per point as per specification No: TMP/TEST.	Point							
43.1	Ground Floor - Head Master Cabin Joint measurement recorded in presence of JE & contractor representative.	Point	119	1			119	100	11,900
43.2	Ground Floor - Office Room 1 Joint measurement recorded in presence of JE & contractor representative.	Point	2	1			2	100	200
43.3	Ground Floor - Office Room 2 Joint measurement recorded in presence of JE & contractor representative.	Point	189	1			189	100	18,900
	Total for Item	Point					310	100	31,000
44 CSR 14-4-1	Item 44 CSR Code 14-4-1 m Excavation of trench in ordinary soil up to 1.5 m depth for cable laying including refilling, ramming and disposal of surplus earth complete as per specification No: TMP/EXC.	m							
44.1	Ground Floor - Head Master Cabin Joint measurement recorded in presence of JE & contractor representative.	m	1	101.41			101.41	275	27,887.75
44.2	Ground Floor - Office Room 1 Joint measurement recorded in presence of JE & contractor representative.	m	1	0.71			0.71	275	195.25
44.3	Ground Floor - Office Room 2 Joint measurement recorded in presence of JE & contractor representative.	m	1	13.20			13.20	275	3,630
	Total for Item	m					115.32	275	31,713
GRAND TOTAL							3,185.62		13,43,175.35

Total measured value: **Rs. 13,43,175.35** | Tendered (estimate) value: **Rs. 13,56,630** | Net deviation: **Rs. -13,454.65**

Certified that the above measurements were jointly recorded at site in the presence of the representative of the contractor, that the quantities shown are as actually executed and that the descriptions, units and rates adopted are as per the current Schedule of Rates (Electrical CSR) applicable to this work.

FORM No. 23 - MEASUREMENT BOOK

Measured by	Checked by	Contractor / Representative	Countersigned
Junior Engineer (Electrical) PWD Electrical Sub-Division	Deputy Engineer (Electrical) PWD Electrical Sub-Division	Signature with date (Joint Measurement)	Executive Engineer (Electrical) PWD Electrical Division

FORM No. 23 - MEASUREMENT BOOK

MB No. MB-01

GOVERNMENT OF MAHARASHTRA | PUBLIC WORKS DEPARTMENT (ELECTRICAL WING)

CSR 2024-25 / Nashik

DEVIATION STATEMENT (Measured vs Tendered)

Quantities measured at site compared with the tendered quantities of the Technical Sanction estimate. Excess / savings are valued at the Master CSR rates to identify items requiring a variation order or excess-item sanction.

CSR Code	Item (short description)	Unit	Rate (Rs.)	Tendered Qty	Measured Qty	Deviation	Dev. %	Excess (+) / Saving (-) Amount (Rs.)
2-1-9	S&E; LED flood light luminaire 100 W, IP66, die cast aluminium housing with... [EXCESS]	Each	4,365	8	10	+2	+25.0%	8,730
1-1-1	S&L; 20 mm dia. PVC conduit concealed in wall / ceiling / slab with necessa...	m	100	620	590.42	-29.58	-4.8%	-2,958
3-1-6	S&E; exhaust fan 250 mm (10 inch) sweep, metal body with powder coating, sh... [EXCESS]	Each	2,470	6	7	+1	+16.7%	2,470
7-2-4	S/E&Term; FR XLPE insulated, galvanised steel formed wire armoured (strip)...	m	1,045	120	117.66	-2.34	-2.0%	-2,445.30
1-3-8	S&E; mains with 3 x 10 sq.mm FRLSH copper PVC insulated wire laid in provid...	m	460	120	116.45	-3.55	-3.0%	-1,633
7-2-2	S/E&Term; FR XLPE insulated, galvanised steel formed wire armoured (strip)...	m	470	85	81.59	-3.41	-4.0%	-1,602.70
1-1-2	S&L; 25 mm dia. PVC conduit concealed in wall / ceiling / slab with necessa...	m	125	340	327.51	-12.49	-3.7%	-1,561.25
1-1-4	S&L; 20 mm dia. 16 gauge rigid steel conduit on surface / concealed with co...	m	275	180	174.34	-5.66	-3.1%	-1,556.50
1-3-6	S&E; mains with 3 x 4 sq.mm FRLSH copper PVC insulated wire laid in provide...	m	220	190	183.23	-6.77	-3.6%	-1,489.40
1-3-3	S&E; mains with 2 x 4 sq.mm FRLSH copper PVC insulated wire laid in provide...	m	150	260	250.80	-9.20	-3.5%	-1,380
14-4-1	Excavation of trench in ordinary soil up to 1.5 m depth for cable laying i...	m	275	120	115.32	-4.68	-3.9%	-1,287
2-1-3	S&E; LED batten luminaire 20 W, 4 ft, 6500 K, polycarbonate body with drive...	Each	1,205	96	95	-1	-1.0%	-1,205
1-3-11	S&E; mains with 4 x 10 sq.mm FRLSH copper PVC insulated wire laid in provid...	m	615	90	88.15	-1.85	-2.1%	-1,137.75
1-1-6	S&F; GI concealed box (8 module) with cover plate for modular switches / so...	Each	220	120	115	-5	-4.2%	-1,100
9-2-3	S&F; GI strip 25 x 6 mm as earth continuity conductor / earth lead with cla...	m	275	90	86.15	-3.85	-4.3%	-1,058.75
14-3-1	Testing and commissioning of internal electrical installation including me...	Point	100	320	310	-10	-3.1%	-1,000
1-9-5	Concealed type 16 A power plug point wiring with 4.0 sq.mm (2 + 1E) FRLSH... [SAVING]	Point	830	10	9	-1	-10.0%	-830
1-5-5	S&F; modular switch 6 A / 16 A on 2 M plate with GI box, connections and ea...	Each	190	64	61	-3	-4.7%	-570

FORM No. 23 - MEASUREMENT BOOK

MB No. MB-01

GOVERNMENT OF MAHARASHTRA | PUBLIC WORKS DEPARTMENT (ELECTRICAL WING)

CSR 2024-25 / Nashik

CSR Code	Item (short description)	Unit	Rate (Rs.)	Tendered Qty	Measured Qty	Deviation	Dev. %	Excess (+) / Saving (-) Amount (Rs.)
1-9-1	Concealed type light / fan / bell point wiring with 1.5 sq.mm (1.5 + 1E) F...	Point	495	84	83	-1	-1.2%	-495
6-2-1	S&F; MCB single pole 6 A to 32 A, C curve, 10 kA breaking capacity, ISI mar...	Each	495	48	47	-1	-2.1%	-495
1-9-10	S&F; modular electronic fan regulator with 2 M plate, GI box, connections a...	Each	435	16	15	-1	-6.2%	-435
1-5-2	S&E; recess type 6 pin plug socket 16 A with switch 16 A combined unit moun... [EXCESS]	Each	405	8	9	+1	+12.5%	405
7-4-1	S&E; brass double compression type cable gland suitable for 20-25 mm cable...	Each	355	24	23	-1	-4.2%	-355
3-1-11	S&F; MS fan hook / clamp box concealed in RCC slab for ceiling fan, with ho...	Each	275	16	15	-1	-6.2%	-275
7-4-2	Supplying and crimping heavy duty aluminium / copper cable lug of suitable...	Each	190	48	47	-1	-2.1%	-190
1-9-2	Concealed type independent plug point wiring with 2.5 sq.mm (2.5 + 1E) FR...	Point	605	22	22	0	+0.0%	0
1-9-3	Concealed type 6 A plug point wiring with 1.5 sq.mm (2 + 1E) FRLSH copper...	Point	540	18	18	0	+0.0%	0
1-9-4	Concealed type twin light point / two way control point wiring with 1.5 sq...	Point	765	12	12	0	+0.0%	0
1-9-6	Concealed type ceiling fan point wiring with 1.5 sq.mm (2 + 1E) FR copper...	Point	630	16	16	0	+0.0%	0
1-9-8	Concealed type call bell point wiring with 1.5 sq.mm (2 + 1E) FR copper wi...	Point	390	4	4	0	+0.0%	0
1-5-1	S&E; recess type 3 pin plug socket 6 A with piano switch 6 A combined unit...	Each	170	24	24	0	+0.0%	0
2-1-1	S&E; LED panel luminaire 18 W, 1200 x 300 mm, surface mounted, 6500 K, CRCA...	Each	2,185	42	42	0	+0.0%	0
2-1-5	S&E; LED bulkhead luminaire 20 W, IP65, die cast aluminium body with toughe...	Each	1,695	12	12	0	+0.0%	0
2-1-12	S&E; LED street light luminaire 120 W, IP66 with programmable driver, surge...	Each	9,365	4	4	0	+0.0%	0
2-1-16	S&E; LED emergency light fitting with 2 hours battery backup, 2 x 6 W LED,...	Each	2,915	8	8	0	+0.0%	0
2-1-17	S&E; LED exit sign luminaire with emergency backup 2 hours, ceiling / wall...	Each	3,000	6	6	0	+0.0%	0
3-1-1	S&E; ceiling fan 1200 mm sweep, 5 star rated, 230 V AC, with down rod, cano...	Each	3,245	16	16	0	+0.0%	0
6-1-1	S&F; SPN distribution board, 8 way, single door, powder coated CRCA sheet e...	Each	3,935	4	4	0	+0.0%	0

FORM No. 23 - MEASUREMENT BOOK

CSR Code	Item (short description)	Unit	Rate (Rs.)	Tendered Qty	Measured Qty	Deviation	Dev. %	Excess (+) / Saving (-) Amount (Rs.)
6-1-3	S&F; TPN distribution board, 8 way, double door, powder coated CRCA sheet e...	Each	8,280	2	2	0	+0.0%	0
6-2-4	S&F; RCCB double pole 40 A, 30 mA sensitivity, 10 kA, complete with connect...	Each	3,305	6	6	0	+0.0%	0
9-1-1	Prov. earthing with galvanized iron earth plate size 60 x 60 x 0.6 cm, bur...	Each	13,095	3	3	0	+0.0%	0
9-1-4	Prov. maintenance free chemical earthing with 3 m long electrode, back fil...	Each	22,030	2	2	0	+0.0%	0
9-3-1	S&E; copper lightning protection spike / air termination rod 1 m long with...	Each	8,815	2	2	0	+0.0%	0
9-4-2	Earth resistance testing with earth tester, recording of results in prescr...	Each	495	5	5	0	+0.0%	0
TOTAL				3,291	3,185.62			-13,454.65

Excess value: Rs. 11,605 | Savings value: Rs. -25,059.65 | Net: Rs. -13,454.65

Note: Items showing excess beyond the permissible variation limit require a formal variation / excess item approval before recording in the final bill.

Prepared by (JE)	Er. Sneha Kulkarni (Junior Engineer (Electrical))	Date of preparation	01/10/2026
------------------	---	---------------------	------------