

Work Abstract

Estimate No. : 1512 of 2025-2026

Name of work : Providing Repairs and Renovation to Street Lights at S. P. Bungalow, Jalgaon.

Sr.No.	Quantity	Item Description	Rate	Unit	Amount
1	55.000	Supplying and erecting PVC insulated PVC round sheathed 1.5 sq.mm (30 no. x 0.25 mm dia.) 3 core flexible multi stranded copper Industrial cable for voltage grade up to 1.1 kV (1-3-14)	61.00	m	3355.00
2	11.000	Supplying and erecting integrated LED street light fitting 60W IP65 & IK08 class with die-cast aluminium housing, 6600 lumens, inbuilt surge protection, 3 years warranty (2-4-5)	4970.00	each	54670.00
3	11.000	Supplying, erecting and marking SPMCB 6A to 32A B-series with rated short-circuit breaking capacity (5-3-3)	173.00	each	1903.00
4	347.000	Supplying, erecting & terminating FR XLPE insulated galvanised steel wire armoured cable (7-1-5)	127.00	m	44069.00
5	303.000	Supplying and laying (including excavation) of suitable width earth trench with sand and brick protection (7-6-9)	210.00	m	63630.00
6	11.000	Providing and erecting galvanised octagonal pole m high (clear height) with base plate and foundation (8-2-12)	15067.00	each	165737.00
7	11.000	Providing and erecting galvanised 1000 mm single arm sword type bracket for street light fitting (8-2-21)	2718.00	each	29898.00
8	12.000	Providing maintenance free chemical earthing with 3 m long electrode, back fill compound, test point and chamber cover (9-1-4)	22030.00	Each	264360.00
9	11.000	Providing and fixing street light feeder pillar foundation considering safe soil bearing capacity (16-3-9)	3684.00	Each	40524.00
		Total			668146.00